



- NOTES:**
1. MATERIAL SHALL MEET REQUIREMENTS AS OUTLINED ON THIS PLAN AND AS FURTHER DESCRIBED IN THESE STANDARDS.
 2. PROVIDE SPACE BETWEEN BUILDING AND PLATE FOR DOWNSPOUT
 3. WHEN DRAIN IS PLACED IN EXISTING SIDEWALK, THE SIDEWALK SHALL BE SAW CUT.

NOTE: THIS PLAN IS NOT A LEGAL ENGINEERING DOCUMENT BUT AN ELECTRONIC DUPLICATE. THE ORIGINAL, SIGNED BY THE ENGINEER AND APPROVED FOR PUBLICATION IS KEPT ON FILE AT THE CITY OF KENT. A COPY MAY BE OBTAINED UPON REQUEST.



		CITY OF KENT ENGINEERING DEPARTMENT	
		SIDEWALK DRAIN FOR BUILDING DOWNSPOUT – TYPE 1	
DESIGNED: COK	SCALE: NONE	STANDARD PLAN	
DRAWN: COK	DATE: 12/2019	5-38	
CHECKED: COK	ENGINEER		
APPROVED:			