



NOTES:

1. SEE STANDARD PLAN 6-36 FOR DOWNTOWN SIDEWALKS.
2. IF TREE IS LOCATED BEHIND THE SIDEWALK, A ROOT BARRIER SHALL BE INSTALLED AT THE EDGE OF THE SIDEWALK.
3. ALL CONSTRUCTION DEBRIS SHALL BE REMOVED FROM TREE PITS. INSTALL 12 INCHES OF PLANTING SOIL AROUND ROOT BALL CONSISTING OF 75% SANDY LOAM AND 25% ORGANICS. FILL REMAINDER OF TREE PIT WITH NATIVE SOIL.
4. IN TREE WELLS, THE ROOT BARRIER SHALL BE PLACED ALL AROUND THE TREE PIT AND STAPLED TOGETHER.
5. FOR BURLAP GROWN TREES THE BURLAP SHALL BE REMOVED AT PLANTING TO A DEPTH OF AT LEAST THE ROOT BALL, DO NOT BURY BURLAP IN PIT.
6. FOR CONTAINER GROWN TREES ALL ROOT BOUND ROOTS SHALL BE CUT AND SEPARATED.
7. NO PRUNING OF THE TREES AT PLANTING.



NOTE: THIS PLAN IS NOT A LEGAL ENGINEERING DOCUMENT BUT AN ELECTRONIC DUPLICATE. THE ORIGINAL, SIGNED BY THE ENGINEER AND APPROVED FOR PUBLICATION IS KEPT ON FILE AT THE CITY OF KENT. A COPY MAY BE OBTAINED UPON REQUEST.

		CITY OF KENT ENGINEERING DEPARTMENT	
		TREE IN PLANTER	
DESIGNED	COK	SCALE	NONE
DRAWN	COK	DATE	9/2020
CHECKED	COK	ENGINEER	
APPROVED		6-55	